

## Addendum

Date: May 22, 2020  
Proj. No.: 19-032  
Project: Kentville Fire Station Renovations  
Addendum No.: #1

---

The following information supersedes the bid documents.

### 1. Changes to the Contract Documents:

1.1 Add to specification section 07 53 23 Ethylene Propylene Diene Monomer (EPDM) – Fully Adhered Roofing System, 1.1:

1.1.1 Minimum 100 MPH wind speed warranty is to be included in the roofing system warranty package.

1.2 Add the following to specification section 08 62 10 Skylights:

1.2.1 Manufacturer's Warranty:

1.2.1.1 Skylights are to come with Manufacturer's standard warranty, outlining that the Manufacturer will repair or replace skylight components that fail under normal use within the specified warranty period.

1.2.2 Dome Type: Double dome, polycarbonate.

1.2.3 Curb Type: Aluminum curb, double wall, self-flashing, factory insulated.

1.3 Add approved alternate to specification section 08 62 10 Skylights:

1.3.1 Velux Dynamic Dome Skylight, 48" x 48".

1.3.2 CD3 double dome, LuxGuard polycarbonate.

1.3.3 CCAM Curb: Factory insulated double wall, self-flashing, aluminum, 16" height and 2.75" integrated mounting flange.

### 2. Clarifications:

2.1 The proponent Bond cheques are to be made out to:

Kentville Volunteer Fire Department

463 Main Street,

Kentville, NS

B4N 1K9

**End of Addendum #1**